

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
JONESTOWN RD @ RIVERSIDE DR
PROJECT NO. 2018028
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3%)	1	LS		
MP-5.02.8(pb)	8" HDPE DIPS (DR 17) ALL DEPTHS	1064	LF		
MP-5.02.8(p)	8" SDR26 HEAVY WALL PVC, INCLUDING BEDDING, ALL DEPTHS	1158	LF		
MP-5.02.6(p)	6" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	60	LF		
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	170	LF		
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	9	EA		
MP-5.03.4(d)	4' DIAMETER DROP MANHOLE	1	EA		
MP-5.03.4(sh)	4' DIAMETER SHALLOW MANHOLE TYPE I	2	EA		
MP-5.04.4(s)	4' ADDITIONAL MANHOLE DEPTH	12	VF		
MP-5.04.4(d)	4' ADDITIONAL DROP MANHOLE DEPTH	5	VF		
MP-5.05.4(p)	8" X 8" X 4" PVC WYE	13	EA		
	8" X 8" X 6" PVC WYE	1	EA		
MP-5.06.4	4" CLEANOUT ASSEMBLY	14	EA		
MP-5.06.6	6" CLEANOUT ASSEMBLY	2	EA		
MP-5.07	PLUG AND ABANDON SEWERLINE	2	EA		
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	2	EA		
MP-5.10	CONNECT TO EXISTING MANHOLE	1	EA		
MP-5.12	PIPE EMBEDMENT MATERIAL	90	CY		
MP-5.13	COMPACTED AGGREGATE BASE COURSE	65	CY		
MP-5.14	SELECT BACKFILL MATERIAL	275	CY		
MP-5.15	ROCK EXCAVATION	275	CY		
MP-5.18.1	EROSION CONTROL - SILT FENCE	280	LF		
MP-5.19	GRAVEL SURFACE DRIVEWAY REPAIR	58	SY		
MP-5.20	SERVICE LINE EXPLORATORY DIG	3	EA		

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
JONESTOWN RD @ RIVERSIDE DR
PROJECT NO. 2018028
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.21.4(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I- 19.0 B) 4" DEPTH	256	SY		

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
JONESTOWN RD @ RIVERSIDE DR
PROJECT NO. 2018028
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	850	SY		
MP-5.21-1.5(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 1.5" MIN. DEPTH (DRIVEWAYS)	52	SY		
MP-5.23	CONCRETE DRIVEWAY REPAIR OR REPLACEMENT, TO MATCH EXISTING	19	SY		
MP-5.25	HAND PLACED ASPHALT CURB	230	LF		
MP-5.25.1	ASPHALT SPEED BUMP (8" WIDE X 6" TALL)	1	EA		
MP-5.33	REMOVE MANHOLE AND PLUG LINES	1	EA		
	TOTAL BID PRICE				\$
TOTAL WRITTEN BID PRICE _____ and _____/100 dollars.					