

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
Old County Home Rd Private Sewer Rehabilitation Project No. 2015221
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3% MAX)	1	LS	\$	\$
MP-5.02.8(d)	8" DIP (CLASS 350) ALL DEPTHS	1704	LF	\$	\$
MP-5.02.18(d)	18" DIP (CLASS 350) ALL DEPTHS	506.68	LF	\$	\$
MP-5.02.12(d)	12" DIP (CLASS 350) ALL DEPTHS	2293	LF	\$	\$
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEL	1500	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	28	EA	\$	\$
MP-5.03.4(d)	4' DIAMETER DROP MANHOLE 0-6 FT.	3	EA	\$	\$
MP-5.04(s)	ADDITIONAL STANDARD MANHOLE DEPTH	123	VF	\$	\$
MP-5.04(d)	ADDITIONAL DROP MANHOLE DEPTH	22	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DI WYE	12	EA	\$	\$
MP-5.05.4(b)	18" X 18" X 4" DI WYE	3	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	65	EA	\$	\$
MP-5.18.1	SILT FENCE	40	LF	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	14	EA	\$	\$
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	4	EA	\$	\$
MP-5.10	CONNECT TO EXISTING MANHOLE	1	EA	\$	\$
MP-5.12	PIPE EMBEDMENT MATERIAL	44	CY	\$	\$

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
Old County Home Rd Private Sewer Rehabilitation Project No. 2015221
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.13	COMPACTED AGGREGATE BASE COURSE	440	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	1600	CY	\$	\$
MP-5.15	ROCK EXCAVATION	1500	CY	\$	\$
MP-5.19	GRAVEL SURFACE DRIVEWAY REPAIR	500	CY	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	30	EA	\$	\$
MP-5.21.11(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.	1200	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE	7050	SY	\$	\$
MP-5.24	CONCRETE CURB & GUTTER REPLACEMENT,	40	LF	\$	\$
MP-5.27	PAVEMENT MILLING 2"	5800	SY	\$	\$
MP-5.34	TREE REPLACEMENT - GENERAL	3	LS	\$	\$
MP-5.48	INSTALLATION OF FORCEMAIN FROM STA 26+58 TO STA 27+45 ACROSS LEICESTER HWY VIA DIRECTIONAL DRILL, INCLUDING ALL FITTINGS	1	LS	\$	\$
	TOTAL BID PRICE				\$
TOTAL WRITTEN BID PRICE _____ _____ and _____ /100 dollars. 					