

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
Toxaway Street Sewer Rehabilitation (Project 2019004)
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3% MAX)	1	LS	\$	\$
MP-5.02.8(d)	8" DIP (CLASS 350) ALL DEPTHS	811	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	12	EA	\$	\$
MP-5.04.4(s)	4' ADDITIONAL STANDARD MANHOLE DEPTH	13	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DUCTILE IRON WYE	15	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	17	EA	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	2	EA	\$	\$
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	4	EA	\$	\$
MP-5.12	PIPE EMBEDMENT MATERIAL	8	CY	\$	\$
MP-5.13	COMPACTED AGGREGATE BASE COURSE	80	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	300	CY	\$	\$
MP-5.15	ROCK EXCAVATION	350	CY	\$	\$
MP-5.18.2	INLET PROTECTION	4	EA	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	17	EA	\$	\$
MP-5.21.6(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B) 6" DEPTH	375	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	1,625	SY	\$	\$
MP-5.25	HAND PLACED ASPHALT CURB	1,000	LF	\$	\$
	TOTAL BID PRICE			\$	
TOTAL WRITTEN BID PRICE _____					
and _____ /100 dollars.					