

Metropolitan Sewerage District of Buncombe County, NC

**TOXAWAY STREET SEWER REPLACEMENT
PROJECT NO. 2019004**

ADDENDUM NUMBER 1

This **ADDENDUM NUMBER 1** is being issued to parties who hold Contract Documents for the subject project with the Metropolitan Sewerage District of Buncombe County. This Addendum Number 1 shall become a part of the Contract Documents and its receipt shall be acknowledged on the bid documents at the time of bidding.

The following additions, revisions and/or clarifications shall be made to the Contract Documents:

- Items MP-5.02.8(d) 8" DIP (CLASS 350) ALL DEPTHS and MP-5.12 PIPE EMBEDMENT MATERIAL of the bid schedule have been deleted.
- Items MP-5.02.8(p) 8" SDR26 HEAVY WALL PVC, INCLUDING BEDDING, ALL DEPTHS and MP-5.02.4(p) 4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING of the bid schedule have been added.
- **PLEASE NOTE: Embedment material shall be included in the item cost of PVC pipe. No additional compensation shall be paid for pipe embedment material.**
- High-velocity manholes have been specified at proposed manholes #4 and #5.
- A new bid schedule and updated plans are attached.

ADDENDUM NUMBER 1 issued this the 8th day of June 2022.

Shaun Armistead, P.E.
Project Engineer
MSD of Buncombe County, NC



SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
Toxaway Street Sewer Rehabilitation (Project 2019004)
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY
Revised per Addendum No. 1

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3% MAX)	1	LS	\$	\$
MP-5.02.8(p)	8" SDR26 HEAVY WALL PVC, INCLUDING BEDDING, ALL DEPTHS	811	LF	\$	\$
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	150	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	12	EA	\$	\$
MP-5.04.4(s)	4' ADDITIONAL STANDARD MANHOLE DEPTH	13	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DUCTILE IRON WYE	15	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	17	EA	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	2	EA	\$	\$
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	4	EA	\$	\$
MP-5.13	COMPACTED AGGREGATE BASE COURSE	80	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	300	CY	\$	\$
MP-5.15	ROCK EXCAVATION	350	CY	\$	\$
MP-5.18.2	INLET PROTECTION	4	EA	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	17	EA	\$	\$
MP-5.21.6(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B) 6" DEPTH	375	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	1,625	SY	\$	\$
MP-5.25	HAND PLACED ASPHALT CURB	1,000	LF	\$	\$
	TOTAL BID PRICE			\$	
TOTAL WRITTEN BID PRICE _____					
_____ and _____ /100 dollars.					